


NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to **3.00 PM on 9/11/2020** from eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite category (any one) for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK- PROVIDING WALL GUARD ACP PANELING AT DINING BLOCK , EXTENSION TO OVER FLOW PIPES AT FACULTY HOUSING , LAMINATION TO STAFF CABINS AND REPAIRING TO STP WATER LINE AT IISER PUNE.

Issue to –

Name and address of the agency –


Executive Engineer

Terms and Conditions:

- 1) The applicant should be eligible contractors registered with anyone CPWD, Maharashtra State PWD, Railways, MES in appropriate category of Civil/Composite Category. Applicant should submit attested or notarized copies of the valid Registration Certificate and Experience Certificate along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
- 2) Time period for completion of work shall be 15 days from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
- 3) Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section , Main Building, IISER PUNE Campus, Dr.Homi Bhabha Road, Pashan, Pune-411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notices-and-eoi>
- 4) All agencies need to submit their quotation in hard copy in sealed envelope containing by suitable means on and before **3 PM on 9/11/2020**. Quotation received after the date & time specified above

Sign & stamp of Agency-

NIQ : Page 1 of 9

Accounts(978)



shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Webcopy) super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document. Commercial envelops of technically qualified bidders shall be opened accordingly . The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

- 5) Bids will be opened **on the same day at 3.30 PM** in the presence of agency or their authorized representatives, if any. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
- 6) Quoted rates should be inclusive of cost of all the materials, labour cost , GST ,all taxes, royalties, cost of fuel, operator , octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid. Decision from competent authority/Engineer In-charge shall be final and binding to bidder in all the matters relating this work.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. Any scaffolding required shall be brought by contractor to complete the work with no cost to IISER Pune. Lowest bidder to furnish water proofing guarantee as per CPWD SOP on Rs.500/- bond paper.
- 8) No advance payment shall be made by IISER Pune. Quoted rates should be including GST , TDS and other applicable taxes . Income Tax and labour cess will be deducted from the bills of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.

Sign & stamp of Agency-

Accounts(978)



NIQ : Page 2 of 9

- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be solely techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
- 11) Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.




Executive Engineer

Encl : - Schedule of Quantity (BOQ) – As per Annexure A

ANNEX-A : Bill Of Quantity

NAME OF WORK- PROVIDING WALL GUARD ACP PANELING AT DINING BLOCK , EXTENSION TO OVER FLOW PIPES AT FACULTY HOUSING , LAMINATION TO STAFF CABINS AND REPAIRING TO STP WATER LINE AT IISER PUNE.

Sr.	Description	Unit	Qty.	Rate in words and figures	Amount
1.00	<p>Providing and fixing aluminium composite panel in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between wo Aluminium sheets (each 0.5mm thick). The aluminium composite panel sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. Aluminium composite panel shall be fixed on wall or frame work in line and level. Approved Makes AlcuBond / Eurobond . Quoted rate shall be including cost of lead, lift, GST, transportation, wastage etc complete. Nothing extra shall be payable separately.</p>	Sqm	90		
2.00	<p>Providing and fixing 75 mm nominal inner dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. Quoted rate shall be including cost of lead, lift, GST, transportation and wastage etc complete. Nothing extra shall be payable separately.</p>	Rmt	20		



Sign & stamp of Agency-

NIQ : Page 4 of 9

Accountst(978)

3.00	Repairing & Fixing of GI specials/ fittings to existing STP line including excavation, removing of existing fittings, fixing fittings by cutting, welding, threading at site. (Rate including of all taxes, GST , wastage, tools, electric power at site, material, labour charges nothing extra shall be payable) Quoted rate shall be including cost of lead, lift, GST, transportation and wastage etc complete. Nothing extra shall be payable separately.				
3.01	GI Nipple 50mm	Each	1		
3.02	GI 50mm Tee	Each	1		
3.03	Brass NRV 50mm	Each	1		
3.04	GI tee 50x90mm	Each	1		
3.05	NRV 63mm	Each	1		
3.06	GI Nipple 63mm	Each	1		
3.07	GI Elbow 63mm	Each	1		
3.08	GI Nipple 90mm	Each	2		
3.09	NRV 90mm	Each	1		



3.1	Elbow 90mm	Each	2		
3.11	Valve Patti 90mm	Each	1		
3.12	Union 90mm	Each	4		
3.13	Reducer tee 90x25mm	Each	25		
3.14	End cap 90mm	Each	1		
3.15	Reducer tee 75x63mm	Each	1		
3.16	Double Nipple 25mm	Each	25		
3.17	Brass valve 25mm	Each	25		
3.18	Elbow 25mm	Each	25		
3.19	Extra for laying 90mm GI line instead of 63mm	Rmt	500		
3.2	Floating Ball Valve 50mm dia Parmar/water tech/Paryag	Each	6		
3.21	PVC Bib Cock Paryag/Parmar/water tech	Each	12		

Sign & stamp of Agency-



NIQ : Page 6 of 9

Accountsl(978)

4.00	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : Quoted rate shall be including cost of lead, lift, GST, transportation and wastage etc complete. Nothing extra shall be payable separately.				
4.01	150 mm diameter Class II	Each	4		
4.02	100 mm diameter Class II	Each	4		
5.00	Making Design, Drawings, lay out Manufacturing, assembling, transporting & Placing in position knock down modular custom made furniture shall be supplied in factory packed duct and water repellent packing form and shall be fixed at site and placed in different rooms such as Trophy Display unit, Gym Shelf with bottle holder & storage unit for sports equipment's etc. as per drawings/layouts, tech specification & direction of Engineer-in-charge. In general all outer exposed edges of all panels shall be covered sealed with 2mm thick PVC edge banding tape. All Joinery fabrication work shall be done with minifix fittings (Hettich, Aries, Efficient cadget Ltd. or eq.) Plastic / stainless Steel dowels, Screws, washers in approved factory supplying minifix, closing loaded hinges multipurpose lock, SS handles. etc. Quoted rate shall be including cost of lead, lift, GST, transportation and wastage etc complete. Nothing extra shall be payable separately.				
5.01	Providing & Fixing 1mm thick decorative lamination approved colour shade design pattern laminate sheet Marino or equivalent approved make on existing ply wood surface with required adhesive smooth finishing etc. all complete as per direction of Engineer-in-charge. (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable)	Sqm	60		

Sign & stamp of Agency-



NIQ : Page 7 of 9

Accounts(978)

5.02	Providing & Fixing 0.8 mm thick decorative lamination approved colour shade design pattern laminate sheet Marino or equivalent approved make on existing ply wood surface with required adhesive smooth finishing etc. all complete as per direction of Engineer-in-charge. (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable)	Sqm	15	
5.03	Providing & Fixing PVC edge Lipping Patti 25mmx3mm thk to edges on existing ply wood surface of Rehau or equivalent approved make, shade fixing with machine in factory etc. all complete as per direction of Engineer-in-charge. (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable)	Rmt	100	
5.04	Providing & Fixing PVC edge Lipping Patti 40mmx3mm thk to edges on existing ply wood surface of Rehau or equivalent approved make, shade fixing with machine in factory etc. all complete as per direction of Engineer-in-charge. (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable)	Rmt	50	
5.05	Providing and fixing Shelf button of HETTICH, ARIES, EFFICIENT GADGETS Ltd. or equivalent make as required for joinery work for joining particle board at right angle for fabrication of furniture items.	Nos.	156	
5.06	Providing and fixing Push magnet of approved sample & make as required for joinery work for joining particle board at right angle for fabrication of furniture items. Push magnet	Each	10	
5.07	Providing & fixing of SS auto closing hinges of Heitch/EBCO/Haffle make or equivalent approved make by engineer-in-charge (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable)	Each	28	



5.08	Providing & fixing of 50mm SS door hinges of approved make & sample by engineer-in-charge (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable)	Each	9	
5.09	Providing & fixing of 50mm SS baby latch of approved make & sample by engineer-in-charge (Rate is inclusive of all the taxes, GST, Materials, Labours, wastage, carriage, loading, unloading and operation & nothing extra shall be payable).	Each	3	
Total				



(Signature)
EXECUTIVE ENGINEER,
ISER, Pune