



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)
IISER Pune Campus, Dr. Homi Bhaba Road, Pune-411 008.
Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2017-18/ 113

Dated 30/7/2018

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on 6/8/2018 from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for Civil/ (B&C) works for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

Name of work : Providing main entry doors with glass panel for dining block , supply and fixing of glass door panels at IISER Pune

Issue to –

Name and address of the agency –


30/07/18
Executive Engineer,
IISER Pune

Terms and Conditions:

- 1) The applicant should be registered with CPWD in western region, Maharashtra State PWD, MES, Railways in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the valid registration certificate along with quotation.
- 2) Time period for completion of work shall be 7 (Seven) days from the date of placing the work order by IISER Pune. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days before a day of submission date of quotation.
- 3) Quotation can be obtained from IISER PUNE Engineering office at Main Building between 10 AM to 4 PM on all working days before date of submission. Applicant may quote by downloading quotation document from IISER PUNE website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 6/8/2018. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . The bid shall be submitted in the original



bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder.

- 5) Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as 'Conditional Quotation' and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , GST , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work.

The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.

No advance payment shall be made by IISER Pune.

Quoted rates should be including GST , TDS and other applicable taxes and cess will be deducted from the bills of the work as applicable.

- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurements and abstract sheet to IISER PUNE within 30 days from completion of work.


30/07/18
Executive Engineer,
IISER Pune

Encl : - Schedule of Quantity (BOQ) – As per Annexure A

Sign & stamp of Agency-



ANNEX-A

NAME OF WORKS : PROVIDING MAIN ENTRY DOORS WITH GLASS PANEL FOR DINING BLOCK , SUPPLY AND FIXING OF GLASS DOOR PANELS AT IISER PUNE.


ITEM NO	DESCRIPTION	QUANTITY	UNIT	RATES IN WORDS AND FIGURES	AMOUNT
1	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) . Powder coated aluminum (minimum thickness of powder coating 50 micron); Quoted rate shall be including lead , lift , shifting, wastage , testing sample , insurance , taxes, duties transportation , GST etc complete. Nothing extra shall be paid separately.				
1.01	For fixed portion , Powder coated aluminum (minimum thickness of powder coating 50 micron)	50.0	kg		
1.02	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). Powder coated aluminum (minimum thickness of powder coating 50 micron)	125.0	kg		



2	Providing and fixing Heavy Duty double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness. Quoted rate shall be including lead , lift , shifting, wastage , testing sample , insurance , taxes, duties transportation , GST etc complete. Nothing extra shall be paid separately. Approved Make : Dorma/Hafle/Godrej	6.0	each		
3	Providing and fixing 100mm brass locks (best make of approved quality) for aluminum doors including necessary cutting and making good etc. complete. Quoted rate shall be including lead , lift , shifting, wastage , testing sample , insurance , taxes, duties transportation , GST etc complete. Nothing extra shall be paid separately. Approved Make : Dorma/Hafle/Godrej	3.0	each		
4	Providing and fixing SS 304 300mm D type handle pair etc complete as per direction of Engineer-In charge. Quoted rate shall be including lead , lift , shifting, wastage , testing sample , insurance , taxes, duties transportation , GST etc complete. Nothing extra shall be paid separately. Approved Make : Dorma/Hafle/Godrej	6.0	each		
5	Providing and fixing aluminum tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete Quoted rate shall be including lead , lift , shifting, wastage , testing sample , insurance , taxes, duties transportation , GST etc complete. Nothing extra shall be paid separately. Size: 150 x10 mm	6.0	each		
6	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminum snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness. Quoted rate shall be including lead , lift , shifting, wastage , testing sample , insurance , taxes, duties transportation , GST etc complete. Nothing extra shall be paid separately.	20.0	sqm		



7	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Quoted rates shall be including GST , labour, lead , lift, transportation etc complete. Nothing extra shall be paid separately.	150.0	kgs		
	Supply and fixing of glass door panels at IISER Pune.				
8	Supply and installation of Toughen glass door of 12 mm thick by taking actual measurement of opening available at site , as per direction of Engineer In-charge , etc complete. Quoted rate shall be including of transportation , lead , lift , shifting of glass to the actual site of work, fixing of door in position , fixing of patch fittings, handle , pivot , floor spring etc complete including making provisions for approved door fittings in toughen glass. Nothing extra shall be paid separately. Actual area of glass panel installed at site shall be measured for payments. (For 6 Doors - 1.0 X 2.4 M size)	15.0	sqm		
9	Supply and installation of Toughen glass panel 12 mm thick by taking actual measurement of opening available at site, as per direction of Engineer In-charge , etc complete. Quoted rate shall be including of transportation , lead , lift , shifting of glass to the actual site of work, fixing of panel in position , fixing fittings/silmline/wide line section etc complete, etc complete. Nothing extra shall be paid separately. Actual area of glass panel installed at site shall be measured for payments. (For 1 Opening - 1.0 X 2.4 M size)	2.5	sqm		
10	Providing and fixing laminated glass panel in sliding door with laminated glass 13.52 mm thick and having 6 mm thick as outer panel and 6 mm thick as inner panel with interlayer of 1.52 mm thick PVB - sentry plus of Dubond make i/c making holes and rounding of edges etc complete as per direction of Engineer in charge. Both panels are toughen glass. Area of glass fixed at site shall be measured for payments (2 Panels of 1.5 X 3.0 M)	10.0	sqm		
11	Supply and installation of Semi-transparent film on glass of 3M/Garware in approved pattern.	15.0	sqm		
TOTAL					


 Executive Engineer, IISER Pune

