



WEBCOPY
भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE

(An Autonomous Institution, Ministry of Human Resource Development, Govt. of India)
IISER Pune Campus, Dr. Homi Bhaba Road, Pune-411 008.
Ph No 020 2590 8001 Fax 020 2588 7499 / 2589 8022

No: 54(2) /IISER/Pune/2017-18/352

Dated 17/11/2017

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on 24/11/2017 from approved and eligible contractors registered with CPWD, Maharashtra State PWD, Railways, MES in appropriate category for Civil/ (B&C) works for the work mentioned below. The quotations will be opened at 3.30 PM on the same day.

NAME OF WORK : AGUMENTATION WORKS IN GROUND FLOOR A BIOLOGY FOR JU LAB AT MAIN BUILDING AT IISER PUNE. SH: CIVIL WORKS QUOTATION NO. : /IISER/PUNE/2017-18

Issue to –

Name and address of the agency –

IISER Pune

Terms and Conditions:

- 1) The applicant should be registered with CPWD in western region, Maharashtra State PWD, MES, Railways in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the valid registration certificate along with quotation.
- 2) Time period for completion of work shall be 15 (Fifteen) days from the date of placing the work order by IISER Pune. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days before a day of submission date of quotation.
- 3) Quotation can be obtained from IISER PUNE Engineering office at Main Building between 10 AM to 4 PM on all working days before date of submission. Applicant may quote by downloading quotation document from IISER PUNE website.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 24/11/2017. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ . The bid shall be submitted in the original

WEBCOPY

bid document (as issued by the IISER, Pune) super scribing the name of work. Rates quoted in the words shall be treated as final for deciding L1 bidder.

- 5) Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as 'Conditional Quotation' and shall be summarily be rejected by IISER PUNE.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , GST , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications , agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work.

The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.

No advance payment shall be made by IISER Pune.

Quoted rates should be including GST , TDS and other applicable taxes and cess will be deducted from the bills of the work as applicable.

- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 11) L1 Agency to submit actual measurements and abstract sheet to IISER PUNE within 30 days from completion of work.

IISER Pune

Encl : - Schedule of Quantity (BOQ) – As per Annexure A

Sign & stamp of Agency-

WEBCOPY

ANNEX-A : SCHEDULE OF QUANTITY (BOQ)

NAME OF WORK : AGUMENTATION WORKS IN GROUND FLOOR A BIOLOGY FOR JU LAB AT MAIN BUILDING AT IISER PUNE. SH : CIVIL WORKS

ITEM NO	DESCRIPTION	QUANTITY	UNIT	RATE IN WORDS AND FIGURES	AMOUNT
1	<p>Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) .Powder coated aluminum (minimum thickness of powder coating 50 micron). Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Make for basic Aluminum Extrusions : JINDAL/BARUKA/Indian Aluminum Co. / Hindalco.</p>				
1.1	<p>For fixed portion : Powder coated aluminum (minimum thickness of powder coating 50 micron).Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.</p>	275.00	kg		

WEBCOPY

1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots/Sliding and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminum (minimum thickness of powder coating 50 micron) Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.	75.00	kg		
2	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Makes : Godrej/Dorma/Geze/Hafele/Hardwyn	5.00	each		
3	Providing and fixing 100mm brass locks (best make of approved quality) for aluminum doors including necessary cutting and making good etc. complete. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Makes : Godrej/Dorma/Geze/Hafele/Hardwyn	4.00	each		
4	Providing and fixing Stainless Steel D handle of 300mm size etc. complete pair of in-out handle as per direction of Engineer In-charge. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Makes : Godrej/Dorma/Geze/Hafele/Hardwyn	5.00	pair		

WEBCOPY

5	Providing and fixing aluminum tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm. Approved Makes Godrej/Dorma/Geze/Hafele/Hardwyn	5.00	each		
6	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. (Cost of aluminum snap beading shall be paid in basic item): With Toughen glass panes of 10 mm thickness Approved Make : Float Glass India Ltd / Modiguard/ Saint Gobin	35.00	sqm		
7	Providing and fixing semi transparent Frosted texture film to glass Door/Window as per direction of Engineer In-charge. Film shade and pattern should be got approved from Engineer In-charge before taking-up work. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Makes : 3M / Garware /Equivalent.	25.00	sqm		
8	Providing and fixing Blackout Film to glass door/window as per direction of Engineer In-charge. Film shade and pattern should be got approved from Engineer In-charge before taking-up works. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Makes : 3M / Garware /Equivalent.	25.00	sqm		
9	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and	70.00	sqm		

WEBCOPY

	directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side. Approved Make : Marino/Century				
10	Wall and ceiling painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work. Quoted rate shall be including all taxes , duties , GST, etc complete. Quoted rate shall be including complete cleaning of floor , skirting , glass panels from paint spots etc complete. cleaning Nothing extra shall be paid separately. Approved Make : Asian Paints/Berger / Nerolac	400.00	sqm		
11	Removal and re-fixing of modular false ceiling of size 595X595 along with grid system as directed by Engineer in charge. Rate shall be inclusive of scaffolding etc complete. Nothing extra shall be paid separately.	25.00	sqm		
12	Providing and fixing modular false ceiling of Armstrong Bioguard/Dune suitable for lab application, confirming to the following specification. Size of the boards:595 X 595 X 15mm with tegular edge with 24mm wide "T" grid. Free ends of tees shall be mounted with quick release high tensile spring steel clips to provide a plug in positive lock for easy removal without tools. Suspension points shall not exceed centre to centre distance of 1200 - 1250 mm and shall be professionally executed with 4-mm GI suspension rod and adjustable J-bolt. The entire sillout grid system shall be designed to bear a distributed load of minimum 18 kg/sqm. The rate quoted for any of the Modular false ceiling system including tiles , removal of old grid , tiles and disposing within IISER PUNE campus , rate shall include providing necessary cut-outs for all sized Light fixtures, AC diffuser, dampers & linear grilles, Smoke detectors, Speakers etc., and any other openings to be made in the false ceiling as directed by Engineer in charge.	10.00	sqm		

WEBCOPY

	Rate shall be inclusive of cost of all the materials, labour all taxes, octroi etc. Approved Make : Armstrong Bioguard/DUNE.				
13	Supplying and installing following size of perforated Hot Dipped Galvanized Iron cable tray (galvanization thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. full threaded suspenders of 10mm diameter and 2500mm length including G.I. bolts & nuts, M6 fastener etc. as required. Size 300 mm width X 50 mm depth X 1.6 mm thickness. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.	25.00	meter		
14	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats including priming coat on new work. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately. Approved Make : Asian Paints/Berger / Nerolac	30.00	sqm		
15	Supply , installation , testing and commissioning water supply and drain piping to wash basin. Water supply piping shall be of 25mm dia CPVC and one CPVC valve at source and other below sink including bends, MTA, FTA etc complete. Drain piping shall be in 50 mm diameter including bend , solvent etc complete. Quoted rate shall be including providing and fixing suitable type connector to stainless Steel water line etc complete. Minimum length of CPVC and PVC piping shall be 4 meter each. Quoted rate	2.00	Job		

WEBCOPY

	shall be including all taxes , duties , GST, etc complete. Nothing extra shall be paid separately.				
16	Cutting of vitrified flooring tiles of 50mm wide and 100mm depth by tile cutter machine in line so as avoid damage to the adjoining tiles and laying of PVC conduits of dia up to 25mm under floor with bed of cement mortar 1:3 (1 cement : 3 coarse sand) . Quoted rate shall be including of supply and installation of matching shade 600X600 vitrified tiles inlays etc complete as per direction of Engineer In-charge including join filling including pointing in white cement mixed with pigment of matching shade complete. Quoted rate shall be including lead , lift, GST, labour, material etc complete. Nothing extra shall be paid separately.	5.00	meter		
17	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Quoted rates shall be including GST , labour, lead , lift , transportation etc complete. Nothing extra shall be paid separately.	50.00	kgs		
				TOTAL	

IISER PUNE