

Date of Issue : 22 June 2020

CORRIGENDUM-1

UNIT OF MEASUREMENT

NAME OF WORK:- :- DESIGN, SUPPLY, INSTALLATION, TESTING, COMMISSIONING AND MAINTENANCE OF RO WATER PLANTS AT IISER PUNE. NIT NO : 3/IISER/PUNE/2020-21

CORRIGENDUM

BOQ, Page-3, Item No- 1.07, Technical Specification of item revised, No change in unit of measurement and quantity.

As per BOQ	To be read as
Supply , installation , lifting , shifting and commissioning of triple layer virgin material , water tank for drinking water purpose of 100% UV stabilized PVC material , IS : 12701 marked with Algae formation protection material , moulded in	Supply , installation , lifting , shifting and commissioning of four layer virgin material , water tank for drinking water purpose of 100% UV stabilized PVC material , IS : 12701 marked with Algae formation protection material , moulded in
seamless perfection with well packed triple layer threaded lid. Quoted rate shall including taking tank to the approved location upto 36 meter height by manual or mechanical means or as per instruction of Engineer In charge , supply and installation three GI tank nipple for Inlet-Outlet- Cleanout by making appropriate holes by machine etc complete. Quoted rate shall be including labour , material , lifting, shifting, all taxes, duties , GST etc complete. Nothing extra shall be paid seperatly. Capacity of tank shall be as per instruction of Engineer In-charge.	seamless perfection with well packed four layer threaded lid. Water tank shall be made-up of 100% food grade material with heat reflective coating . Quoted rate shall including taking tank to the approved location up to 36 meter height by manual or mechanical means or as per instruction of Engineer In-charge , supply and installation three GI tank nipple for Inlet-Outlet-Cleanout by making appropriate holes by machine etc complete. Quoted rate shall be including labour , material , lifting, shifting, all taxes, duties , GST etc complete. Nothing extra shall be paid separately. Capacity of tank shall be as per instruction of Engineer In- charge. Approved Make Sintex Titus / Plasto Gold

Bidders are requested to take note of it and quote accordingly.

The original tender document and conditions already in e-tender stands modified to the extent of modifications defined in above **CORRIGENDUM : 1 UNIT OF MEASUREMENT** and shall form part of tender document. The bidders are requested to submit duly signed the corrigendum and all its enclosures along with the tender document on due date of submission of tender. The bidders are further requested to take note of above corrigendum and quote rates accordingly. E-copy of the Corrigendum-1 is uploaded on https://eprocure.gov.in/eprocure/app and Institute website at http://www.iiserpune.ac.in/links/tender-notices-and-eoi

Registrar and Engineer In-Charge IISER Pune